

100 Days is Phase 1, Phase 2, and some of Phase 3

Rest of the year is maintaining progress and implementing Phase 3 and possibly 4.

Phase 1: Organize (Infrastructure phase)

- Collect bills from at least 2 years prior

- Set up file share system (we use Drive)

- Set up Portfolio Manager

- Asset Mapping

- Goal Setting

- BEGIN researching related grants and programs available in your area

Phase 2: Do we need to use it? (mostly free)

- Set up room by room information document

- Inventory how you use your building

- Deputize people to turn off lights and thermostats

- Have conversations about when and where you meet

- Program thermostats

- Motion sensor lights?

Phase 3: Can it be used more efficiently? (slight to major cost)

- Energy Audit

- LED Light Bulbs

- Change AC air filters

- Calk Windows

- Insulation (walls, ceiling, outlets)

- Upgrade windows

- Upgrade HVAC (heat pumps?)

- Upgrade lighting

Phase 4: Are there alternate sources for energy? (major cost)

- Solar, geothermal, hydroelectric... depending on geography and facility